

# PARKS CONSTRUCTION



Registered House-Builder

LINNYSHAW INDUSTRIAL ESTATE  
MOSS LANE, OFF SHARP STREET  
WALKDEN  
MANCHESTER  
M28 3JS  
FAX/PHONE : 0161 799 9131  
Email : info@parksconstruction.co.uk  
www.parksconstruction.co.uk

VAT REGISTRATION  
No. 148 2599 35

Job Title	Main Activities
Groundwork Operative	Installation / removal of Standard Street Furniture Foundations

Sub Activities (break down of Main Activities)	Hazard/s -potential to cause harm (see categories list)	Existing Control Measures	Risk Level (High, Medium, Low)	Additional Controls / Comments	Risk Level (after)
Signing and guarding of site/ vehicle.	Being struck by vehicle	Operatives trained to NRASWA Chapters 1 & 2. Appropriate PPE to be worn	High	Operatives to face the traffic flow when positioning signs and cones.	Medium
Public Safety	Insufficient pavement width access. Pedestrians wandering into site.	Work area totally protected from public access and signing and guarding to Chapter 8	Low	Operatives to assist pedestrians past barriers if required assistance.	Low
Site Conditions	Risk of injury through tripping, loosing footing down side of shallow excavations or falls.	Site to be cleared of spoil and backfill material stored away from working corridors.	Low	Operatives to keep site clean and tidy.	Low
Site Excavations	Damage to electricity and gas pipes	Operatives trained to NRASWA for excavations and cable detection.	High	Excavation in areas of known services to be hand dug with care.	Medium
Electricity	Electric shock	Training given to operatives in basic electrical awareness.	Medium	Operatives to avoid contact with cable. Electrician to be called if cable requires making safe or moving.	Low

Pouring Concrete	Danger of concrete splashes resulting in burns.	Operatives trained in first aid.	Medium	Operatives to wear suitable clothing and eye protection.	Low
Manual Handling	Risk of pulls, sprains, strains etc.	Operatives trained in Manual Handling.	Medium	When possible mechanical means of lifting should be used.	Low
Using Power Tools	Electric shock, burns, abrasions, cuts. Noise of equipment.	Operatives trained in the use of abrasive wheels. All equipment tested and maintained in good working order. PPE to be worn	Low	Power tools battery operated or 110V Certificate servicing of equipment	Low

<b>Sub Activities</b> <small>(break down of Main Activities)</small>	<b>Hazard/s</b> <small>-potential to cause harm (see categories list)</small>	<b>Existing Control Measures</b>	<b>Risk Level</b> <small>(High, Medium, Low)</small>	<b>Additional Controls / Comments</b>	<b>Risk Level (after)</b>
Driving	Operation of vehicles	Drivers Policy/Procedures handbook supplied; Periodic review of driving licences; Drug & Alcohol policy in place.	Low	Review as necessary	Low

This "Job Risk Assessment" will be issued to each Operative who is required to carry out this Task (job). The Line Manager/Supervisor of the Operative will sign below to say that they have explained to the Operative the associated risks and current control measures required to be undertaken. A copy will be held on file by the Line Manager/Supervisor.

The Operative will sign below to say that they understand the requirements of this assessment and have been issued with a copy.

<b>Person</b>	<b>Print Name</b>	<b>Signature</b>	<b>Date</b>
Line Manager/Supervisor	S PARKS		
Groundwork Operative			